BIL SOLUTIONS
bilsolutions.co.uk

CHECKLIST

Radon measurement checklist for your home

- [ ] Choose the lowest occupied level of your building for initial testing
- [ ] Select a detector type that matches your budget and measurement timeframe
- [ ] Place the detector at breathing height, away from draughts and external walls
- [ ] Record the deployment date, time and room conditions
- [ ] Keep windows and doors closed for the period specified in the detector instructions
- [ ] Seal the detector at the end of the exposure period and note the time
- [ ] Send passive detectors to the laboratory within the timeframe given
- [ ] Compare your result to the action level in your jurisdiction
- [ ] Consider remedial measures if your reading exceeds the action level
- [ ] Repeat the measurement after any remediation work to verify effectiveness